



चुलाचुली गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



पत्र संख्या: ०८११०८२
च.नं.

कोशी प्रदेश, नेपाल

मिति: २०८२/०२/२२

प्रस्ताव पेश गर्ने सम्बन्धमा प्रथम पटक सुचना प्रकाशन मिति २०८२/०२/२०

प्रस्तुत विषयमा चुलाचुली गाउँपालिकाको **Bidhwa Khola Tatabandhan Piyakurel Gaun River Protection Works** को यस सुचना साथ सलग्न राखिएको **BOQ** बमोजिम के कति दरेटमा गर्न सकिने हो? तपशिल बमोजिमका कागजातहरु सहित मिति २०८२/०२/२६ गते कार्यालय समयभित्र चुलाचुली गाउँपालिकाको कार्यालयमा प्रस्ताव पेश गर्नुहुन यस गाउँपालिकाको मौजुदा सुचीमा सुचिकृत रहेका सम्पूर्ण निर्माण व्यावसायी/फर्महरुलाई सुचित गरिन्छ।

पेश भएको प्रस्तावहरुमध्ये प्रचलित सार्वजनिक खरिद ऐन २०६३ तथा सार्वजनिक खरिद नियमावली २०६४ बमोजिम न्यूनतम मुल्यांकित सारभुत रुपमा प्रभावग्राही प्रस्तावदातासंग सम्झौताको लागि प्रक्रिया अगाडी बढाइनेछ।

तपशिल :

१. रितपूर्वक भरिएको BOQ
२. कम्पनि दर्ताको प्रमाणपत्र
३. निर्माण व्यावसायी इजाजतको प्रतिलिपि
४. स्थायी लेखा नम्बर(प्यान) दर्ताको प्रतिलिपि
५. आ ब २०८०/८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपि

विकाश वि.क.
प्रमुख प्रशासकीय अधिकृत

विकाश वि.क.
प्रमुख प्रशासकीय अधिकृत

Website: www.chulachulimun.gov.np Email : chulachuli.ruralmunicipality@gmail.com

"कृषि पर्यटन र पूर्वधारमा उन्नति, चुलाचुली गाउँपालिकाको समुन्नति"
"सुनिश्चित बालमैत्री बानी व्यवहार, बालमैत्री चुलाचुली समृद्धिको आधार"

CHULACHULI RURAL MUNICIPALITY
Office of Rural Municipality Executive
Chulachuli Ilam

Koshi Province Nepal

NAME OF PROJECT:-BIDHWA KHOLA TATABANDHAN PIYAKUREL GAUN RIVER PROTECTION WORKS
PROJECT LOCATION:- CHULACHULI 5 ILAM

Bill of Quantity(BOQ)

S.N	Description	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In Numbers	In Words		
1	Supplying and installation of Project information board (4'x3') CGI plane sheet with locally available frame all complete.	LS	1.00				
2	Earthwork in excavation by machine as per instruction of site engineer	Cum	71.40				
3	Supplying of Machine made Heavy coated hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses of with diapharagms, with Lacing wire 2.4 mm, mesh wire 3.0mm and selvedged wire 3.9mm , assembling Gabion boxes mattresses, palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation all complete as per specification.	Cum	117.75				
4	Suppling laying and fixing of Geotextile as per specification of the engineer all complete.	Cum	6.00				
5	Back filling on the side of gabion by locally available soil as per drawing and technical specification and instruction of site engineer in charge.	Cum	82.50				
				Sub Total			
				VAT@13%			
				Total Cost with VAT			

विकास पिक.
प्रमुख प्रशासकीय अधिकृत