



चुलाचुली गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



पत्र संख्या: ०८२/८३
च.नं.




कोशी प्रदेश, नेपाल
फोन नं=९७४६८७२४२५

मिति: २०८२/०९/२०

प्रस्ताव पेश गर्ने सम्बन्धमा प्रथम पटक सूचना प्रकाशन मिति २०८२/०९/२०

प्रस्तुत विषयमा चुलाचुली गाउँपालिकाको **Construction of tallo sukha holi culvert chulachuli -3 ilam** को यस सूचना साथ सलग्न राखिएको **BOQ** बमोजिम के कति दररेटमा गर्न सकिने हो? तपशिल बमोजिमका कागजातहरु सहित मिति २०८२/०९/२७ गते कार्यालय समयभित्र चुलाचुली गाउँपालिकाको कार्यालयमा प्रस्ताव पेश गर्नुहुन यस गाउँपालिकाको मौजुदा सूचीमा सुचिकृत रहेका सम्पूर्ण निर्माण व्यावसायी/फर्महरुलाई सुचित गरिन्छ।

पेश भएको प्रस्तावहरुमध्ये प्रचलित सार्वजनिक खरिद ऐन २०६३ तथा सार्वजनिक खरिद नियमावली २०६४ बमोजिम न्यूनतम मुल्यांकित सारभुत रुपमा प्रभावग्राही प्रस्तावदातासंग सम्झौताको लागि प्रक्रिया अगाडी बढाइनेछ।


राज कुमार शाक्य
प्रमुख प्रशासकीय अधिकृत

तपशिल :

१. रितपूर्वक भरिएको BOQ
२. कम्पनि दर्ताको प्रमाणपत्र
३. निर्माण व्यावसायी इजाजतको प्रतिलिपि
४. स्थायी लेखा नम्बर(प्यान) दर्ताको प्रतिलिपि
५. आ ब २०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि

राजकुमार शाक्य
प्रमुख प्रशासकीय अधिकृत

PROJECT NAME:-CONSTRUCTION OF TALLO SUKHA HOLI CULVERT CHULACHULI 3- ILAM
PROJECT LOCATION:-CHULACHULI-3, ILAM

Bill of Quantity (BOQ)

S.N	Description	Unit	Quantity	Rate (NRs.)		Remarks
				In Numbers	In Words	
1	Road way Excavation in all types of soil by Mechanical Means as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. [SS 905]	cum	34.44			
2	Providing and laying of hand packed stone selling with 150 to 200 mm thick stones and packing with smaller stones on prepared surface as per drawing and technical specifications	cum	12.87			
3	Providing and laying of PCC M: 10 (or 1:3:6 for nominal mix) in foundation complete as per Drawing and Technical Specification	cum	4.97			
4	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% boulders/stones [SS 2421] including formwork and its associates all complete	cum	13.51			
5	Providing, Preparing and Installing form work including necessary supports and removing after completion for walls, vertical plain surfaces class F2 Finish using plywood(For wall up to 3 m height)	Sqm	77.58			
6	Providing and laying, fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification.[SS 2000]	MT	2.43			
7	Providing and laying of Plain/Reinforced Cement Concrete in Structure including formwork complete as per Drawing and Technical Specifications. PCC Grade M 20	cum	9.93			
8	GI pipe 2" diameter for railing post with cutting fabrication and all specifications as per engineer	Rm	14.00			
Sub Total						
VAT@13%						
Total Cost with VAT						

(Signature)
प्रमुख प्रशासक/प्रमुख अभियंता
चुलाचुली नगरपालिका
चुलाचुली-३, इलाम