



चुलाचुली गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय



पत्र संख्या: ०८०१०८१
च.नं.



कोशी प्रदेश, नेपाल

प्रस्ताव पेश गर्ने सम्बन्धमा
प्रथम पटक सूचना प्रकाशन मिति २०८०/११/०८

प्रस्तुत विषयमा चुलाचुली गाउँपालिकाको र कमल गाउँपालिका क्षेत्र अन्तर्गत झापा इलाम सिमाना तिनफन्के होलीमा कल्भर्ट निर्माण एकमुष्ट यस सूचना साथ सलग्न राखिएको BOQ बमोजिम के कति दररेटमा गर्न सकिने हो? तपशिल बमोजिमका कागजातहरु सहित मिति २०८०/११/१४ गते कार्यालय समयभित्र चुलाचुली गाउँपालिकाको कार्यालयमा प्रस्ताव पेश गर्नुहुन यस गाउँपालिकाको मौजुदा सूचीमा सूचिकृत रहेका सम्पूर्ण निर्माण व्यावसायी/फर्महरुलाई सूचित गरिन्छ।
पेश भएको प्रस्तावहरुमध्ये प्रचलित सार्वजनिक खरिद ऐन २०६३ तथा सार्वजनिक खरिद नियमावली २०६४ बमोजिम न्यूनतम मुल्यांकित सारभुत रुपमा प्रभावग्राही प्रस्तावदातासंग सम्झौताको लागि प्रक्रिया अगाडी बढाइनेछ।

तपशिल :

१. रितपूर्वक भरिएको BOQ
२. कम्पनि दर्ताको प्रमाणपत्र
३. निर्माण व्यावसायी इजाजतको प्रतिलिपि
४. स्थायी लेखा नम्बर(प्यान) दर्ताको प्रतिलिपि
५. आ ब २०७९/८० को करचुक्ता प्रमाणपत्रको प्रतिलिपि

केशव कुमार ढकाल
प्रमुख प्रशासकीय अधिकृत
केशव कुमार ढकाल
प्रमुख प्रशासकीय अधिकृत

Chulachuli Rural Municipality
Office of Rural Municipality Executive
Chulachuli Ilam

Koshi Province Nepal
Project Name: Construction of Tinfunke Culvert ward no 4 (Ilam-Jhapa Boarder)
Location: Chulachuli 4, Ilam

Bill of Quantity(BOQ)

Item no	Description	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In Numbers	In Words		
1	Hoarding Board	LS	1.00				
2	Earthwork excavation in foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter backfilling with approved material as per Drawing and Technical Specifications (Depth up to 3 m) by mechanical means	Cu.m	44.24				
3	Providing and laying of boulder stone compaction in foundation and flooring area, packing the joint with coarse sand including watering, compaction by jumper machine, consolidation and dressing up to the approved levels and line all complete as per specification, drawings and instruction of engineer.	cum	6.43				
4	Plain Cement Concrete (PCC) for PCC works: M10 (1:3:6) ratio with nominal concrete mix for foundations, flooring, walls, site development etc with approved quality of cement (ordinary portland cement), sand and stone crushed aggregate (20-40mm) including mixing, transporting, placing, compaction, curing etc. including cost of all materials, all complete as per specification, drawings and instruction of engineer. (Using mixture machine and vibrator)	Cu.m	4.39				
5	P.C.C. 1:1.5:3 work for R.C.C for footing, slabs, lintels, sills and beams.	cum	6.10				
6	Cutting, bending, placing in position as shown in the drawing & binding by GI wire of reinforcement steel bar for RCC works incl. haulage dist. upto 30m.	kg	609.68				

7	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% boulders/stones [SS 2421]	cum	70.29				
8	Formworks: Providing 19mm thick waterproof plywood and steel prop formwork for SLAB concrete works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett including cost of all materials, all complete as per specification, drawings and instruction of engineer. FOR SLAB	Sqm	94.74				
9	2" dia GI pipe	R.m	24.00				
Total Cost							
<u>VAT@13%</u>							
<u>Total Cost with VAT</u>							