



चुलाचुली गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



पत्र संख्या: ०८११०८२
च.नं.

चुलाचुली, इलाम

कोशी प्रदेश, नेपाल

प्रस्ताव पेश गर्ने सम्बन्धमा

प्रथम पटक सूचना प्रकाशन मिति २०८१/०४/३२

प्रस्तुत विषयमा चुलाचुली गाउँपालिकाको वडा नं ३ र ४ विभिन्न सडक खण्डहरूको मर्मत संभारका लागि **Maintenance of Ward 3- 4 Boarder Road and Chumalung-Kirat Chowk Road Ward no 3** क्षेत्र अन्तर्गत एकमुष्ट यस सूचना साथ सलग्न राखिएको **BOQ** बमोजिम के कति दररेटमा गर्न सकिने हो? तपशिल बमोजिमका कागजातहरूसहित मिति २०८१/०५/०६ गते कार्यालय समयभित्र चुलाचुली गाउँपालिकाको कार्यालयमा प्रस्ताव पेश गर्नुहुन यस गाउँपालिकाको **मौजूदा सूचीमा सूचिकृत रहेका सम्पूर्ण निर्माण व्यावसायी/फर्महरूलाई** सूचित गरिन्छ।
पेश भएको प्रस्तावहरूमध्ये प्रचलित सार्वजनिक खरिद ऐन २०६३ तथा सार्वजनिक खरिद नियमावली २०६४ बमोजिम न्यूनतम मुल्यांकित सारभुत रूपमा प्रभावग्राही प्रस्तावदातासंग सम्झौताको लागि प्रक्रिया अगाडी बढाइनेछ।


राज कुमार शाक्य

प्रमुख प्रशासकीय अधिकृत

राज कुमार शाक्य
प्रमुख प्रशासकीय अधिकृत

तपशिल :

१. रितपूर्वक भरिएको BOQ
२. कम्पनि दर्ताको प्रमाणपत्र
३. निर्माण व्यावसायी इजाजतको प्रतिलिपि
४. स्थायी लेखा नम्बर(प्यान) दर्ताको प्रतिलिपि
५. आ ब २०८०/८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपि

CHULACHULI RURAL MUNICIPALITY

Office of Rural Municipal Executive
Chulachuli, Ilam
Koshi Province, Nepal

[Signature]
राज कुमार शर्मा
प्रमुख प्रशासकीय अधिकृत

Bill of Quantity (BOQ)

Project Name: Maintenance of Ward 3- 4 Boarder Road and Chumaling-Kirat Chowk Road Ward no 3



Item no	Description	Unit	Quantity	Rate (NRs.)		Remarks
				In Numbers	In Words	
1.0	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications by mechanical means up to 30m lead	Sqm	4,740.00			
2.0	Providing and laying River bed materials on prepared surface mixing at OMC and compacting to achieve the desired density complete as per Drawing and Technical Specifications by mechanical means	Cum	688.50			
3.0	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer by mechanical means	Cum	3.41			
4.0	Providing and laying of hand pack soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications	Cum	0.73			
5.0	Providing and placing machine mixed cement concrete of M10 for the foundation and footing etc. including compaction, curing, testing etc all complete as per specification	Cum	0.49			
6.0	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 450 mm internal dia. Pipe	R.m	7.50			
Total						
Vat @ 13%						
Grand Total						