



चुलाचुली गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



पत्र संख्या: ०८१०८२
च.नं.



कोशी प्रदेश, नेपाल

प्रस्ताव पेश गर्ने सम्बन्धमा प्रथम पटक सूचना प्रकाशन मिति २०८१/०६/०६

प्रस्तुत विषयमा चुलाचुली गाउँपालिकाको **Hump pipe Installation and Graveling works on chulachuli ward no 3 & 4** को यस सूचना साथ सलमन राखिएको **BOQ** बमोजिम के कति दररेटमा गर्न सकिने हो? तपशिल बमोजिमका कागजातहरु सहित मिति २०८१/०६/१२ गते कार्यालय समयभित्र चुलाचुली गाउँपालिकाको कार्यालयमा प्रस्ताव पेश गर्नुहुन यस गाउँपालिकाको मौजुदा सूचीमा सूचिकृत रहेका सम्पूर्ण निर्माण व्यावसायी/फर्महरुलाई सुचित गरिन्छ।

पेश भएको प्रस्तावहरुमध्ये प्रचलित सार्वजनिक खरिद ऐन २०६३ तथा सार्वजनिक खरिद नियमावली २०६४ बमोजिम न्यूनतम मुल्यांकित सारभुत रुपमा प्रभावग्राही प्रस्तावदातासंग सम्झौताको लागि प्रक्रिया अगाडी बढाइनेछ।

तपशिल :

१. रितपुर्वक भरिएको BOQ
२. कम्पनि दर्ताको प्रमाणपत्र
३. निर्माण व्यावसायी इजाजतको प्रतिलिपि
४. स्थायी लेखा नम्बर(प्यान) दर्ताको प्रतिलिपि
५. आ ब २०८०/८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपि


राज कुमार शाक्य
प्रमुख प्रशासकीय अधिकृत
राज कुमार शाक्य
प्रमुख प्रशासकीय अधिकृत

CHULACHULI RURAL MUNICIPALITY

Office of Rural Municipal Executive
Chulachuli, Ilam
Province no. 1, Nepal

Bill of Quantity(BOQ)

Project Name:- Hump pipe Installation and Gravelling works on chulachuli ward no 3 & 4
Project Location:-Chulachuli ward no 3& 4


राजी कुमार शर्मा
प्रमुख प्रशासकीय अधिकृत

Item no	Description	Unit	Quantity	Rate (NRs.)	Amount in Number	Amount in words	Remarks
1.0	Compacting original ground supporting sub-grade. Loosening of the ground upto a level of 500 mm below the sub-grade level, watered, graded and compacted in layers as per drawings and technical specifications.[SS 1000]	sqm.	210.00				
2.0	Providing and laying River bed materials on prepared surface mixing at OMC and compacting to achieve the desired density complete as per Drawing and Technical Specifications by mechanical means	cum.	126.00				
3.0	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 450 mm internal dia. Pipe	Rm.	80.00				
4.0	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 600 mm internal dia. Pipe	Rm.	27.50				
5.0	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 900 mm internal dia. Pipe	Rm.	5.00				
				Total			
				Vat @ 13%			
				Grand Total			