



# चुलाचुली गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



चुलाचुली, इलाम

पत्र संख्या: ०८०१०८१  
च.नं.

कोशी प्रदेश, नेपाल  
फोन नं=९७४६८७२४२५

## प्रस्ताव पेश गर्ने सम्बन्धमा


प्रथम पटक सुचना प्रकाशन मिति २०८१/०१/०२

प्रस्तुत विषयमा चुलाचुली गाउँपालिकाको वडा नं १ क्षेत्र अन्तर्गत काडसोरे मार्ग र सिचाई मार्ग मर्मत वडा नं १, पापोहाड मार्ग ग्राभेल(वडा नं १), बनेम भवन जाने बाटो ग्राभेल (वडा नं १) बरगाछी मार्ग मर्मत (बरगाछी देबिथान देउराली मार्ग खण्ड वडा नं १), मैनाचुली वैकल्पिक मार्ग र कुमालेवारी भालुकुरे रिड रोड निर्माण तथा मर्मत (वडा नं १), सटके मार्ग ह्युमपाइप कलभर्ट निर्माण (मिन्द्रा होलीमा) वडा नं १, ह्युम पाइप खरिद त दुबानी तथा जडान (वडा नं १) एकमुष्ट यस सुचना साथ सलान राखिएको BOQ बमोजिम के कति दररेटमा गर्न सकिने हो? तपशिल बमोजिमका कागजातहरु सहित मिति २०८१/०१/०९ गते कार्याल समयभित्र चुलाचुली गाउँपालिकाको कार्यालयमा प्रस्ताव पेश गर्नुहुन यस गाउँपालिकाको मौजूदा सुचीमा सुचिकृत रहेका सम्पूर्ण निर्माण व्यावयायी/फर्महरुलाई सुचित गरिन्छ।

पेश भएको प्रस्तावहरुमध्ये प्रचलित सार्वजनिक खरिद ऐन २०६३ तथा सार्वजनिक खरिद नियमावली २०६४ बमोजिम न्युनतम मुल्यांकित सारभुत रुपमा प्रभावग्राही प्रस्तावदातासंग सम्झौताको लागि प्रक्रिया अगाडी बढाइनेछ।

पशिल :

१. रितपूर्वक भरिएको BOQ
२. कम्पनि दर्ताको प्रमाणपत्र
३. निर्माण व्यावसायी इजाजतको प्रतिलिपि
४. स्थायी लेखा नम्बर(प्यान) दर्ताको प्रतिलिपि
५. आ ब २०७९/८० को कर्चुक्ता प्रमाणपत्रको प्रतिलिपि

  
केशव कुमार ठकाल  
प्रमुख प्रशासकीय अधिकृत

**Chulachuli Rural Municipality**  
**Office of Rural Municipality Executive**  
**Chulachuli Ilam**  
**Koshi Province Nepal**



**Name of Project: Ward no 1 Different Roads gravelling works along with hume pipe installation works**

**Location: Chulachuli-1, Ilam**

**Bill of Quantity(BOQ)**

Item no	Description	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In Numbers	In Words		
1	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications by mechanical means up to 30m lead	Sqm	3,408.00				
2	Providing and laying River bed materials on prepared surface mixing without compaction loose gravelling	Cum	511.20				
3	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer by mechanical means	Cum	28.37				
4	Providing and laying of hand pack soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications	Cum	4.40				
5	Providing and placing machine mixed cement concrete of M10 for the foundation and footing etc. including compaction, curing, testing etc all complete as per specification	Cum	3.19				
6	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 300 mm internal dia. Pipe	R.m	15.00				
7	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 450 mm internal dia. Pipe	R.m	5.00				
8	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 900 mm internal dia. Pipe	R.m	10.00				
9	Backfilling works with river bed materials along different location of culvert	Cum	14.00				
<b>Total Cost</b>							
<b>VAT@13%</b>							
<b>Total Cost with VAT</b>							