



पत्र संख्या: ०८०१०८१  
च.नं.

## चुलाचुली गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



कोशी प्रदेश, नेपाल

### प्रस्ताव पेश गर्ने सम्बन्धमा प्रथम पटक सूचना प्रकाशन मिति २०८०/१०/१८

प्रस्तुत विषयमा चुलाचुली गाउँपालिकाको वडा नं ३ र ४ क्षेत्र अन्तर्गत ह्युम पाइप खरिद जडान वडा नं ३ तथा ह्युम पाइप खरिद तथा जडान वडा नं ४ को एकमुष्ट यस सूचना साथ सलग्न राखिएको **BOQ** बमोजिम के कति दररेटमा गर्न सकिने हो? तपशिल बमोजिमका कागजातहरू सहित मिति २०८०/१०/२५ गते कार्यालय समयभित्र चुलाचुली गाउँपालिकाको कार्यालयमा प्रस्ताव पेश गर्नुहुन यस गाउँपालिकाको मौजूदा सूचीमा सूचिकृत रहेका सम्पूर्ण निर्माण व्यावसायी/फर्महरूलाई सूचित गरिन्छ। पेश भएको प्रस्तावहरूमध्ये प्रचलित सार्वजनिक खरिद ऐन २०६३ तथा सार्वजनिक खरिद नियमावली २०६४ बमोजिम न्यूनतम मुल्यांकित सारभुत रुपमा प्रभावग्राही प्रस्तावदातासंग सम्झौताको लागि प्रक्रिया अगाडी बढाइनेछ।

#### तपशिल :

१. रितपूर्वक भरिएको BOQ
२. कम्पनि दर्ताको प्रमाणपत्र
३. निर्माण व्यावसायी इजाजतको प्रतिलिपि
४. स्थायी लेखा नम्बर(प्यान) दर्ताको प्रतिलिपि
५. आ ब २०७९/८० को करचुक्ता प्रमाणपत्रको प्रतिलिपि

*(Signature)*  
केशव कुमार ढकाल  
प्रमुख प्रशासकीय अधिकृत  
केशव कुमार ढकाल  
प्रमुख प्रशासकीय अधिकृत

**Chulachuli Rural Municipality**  
**Office of Rural Municipale Executive**  
**Chulachuli Ilam**  
**Koshi Province Nepal**



**Project Name: Ward no 3 and 4 hume pipe installation Works**  
**Location: Chulachuli-3 and 4, Ilam**

**Bill of Quantity(BOQ)**

Item no	Description	Unit	Quantity	Rate (NRS.)		Amount (NRS.)	Remarks
				In Numbers	In Words		
1	Site clearance of all associated location	L.S	1.00				
2	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer by mechanical means	m <sup>3</sup>	19.40				
3	Providing and laying of hand pack soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications	m <sup>3</sup>	4.88				
4	Providing and placing machine mixed cement concrete of M10 for the foundation and footing etc. including compaction, curing, testing etc all complete as per specification	m <sup>3</sup>	3.10				
5	Providing and laying random rubble stone masonry work in cement sand mortar 1:6 in foundation complete as per Drawing and Technical Specifications	m <sup>3</sup>	24.89				
6	Backfilling works after hume pipe installation using river bed granular materials	m <sup>3</sup>	31.20				
7	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 450 mm internal dia. Pipe	Rm	47.50				

**नेपाल कम्युनिस्ट पार्टी**  
**प्रमुख प्रशासकीय अधिकृत**

OX

*(Signature)*

8	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 600 mm internal dia. Pipe	Rm	32.50				
9	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 900 mm internal dia. Pipe	Rm	15.00				
Total Cost							
VAT@13%							
<u>Total Cost with VAT</u>							



*(Handwritten signature)*

**ಕರ್ನಾಟಕ ಸರ್ಕಾರ**  
**ಪ್ರಮುಖ ಪ್ರशासकीय अधिकारी**

*(Handwritten signature)*